ISBN 0-7729-2543-7

CHLORINATION OF POTABLE WATER SUPPLIES

BULLETIN 65-W-4

UPDATED MARCH 1987

Ontario
Ministry of the Environment

J. Bishop, Director
Water Resources Branch

CHLORINATION OF POTABLE WATER SUPPLIES

BULLETIN 65-W-4

ISBN-0-7729-2543-7

Drinking Water Section
Water Resources Branch
Updated March 1987

CHLORINATION OF POTABLE WATER SUPPLIES

INDEX

		Page
1.0	INTRODUCTION	1
1.1	Purpose of Bulletin	1
1.2	When is Disinfection Required?	1
1.3	Types of Chlorination	1
2.0	EQUIPMENT	3
2.1	Capacity	3
2.2	Duplicate Equipment	3
2.3	Chlorinators and Controls	3
2.4	Gas Chlorination	4
2.4.1	Building Design	4
2.4.2	Safety Equipment	5
2.5	Hypochlorite Chlorination	6
2.5.1	Safety Procedures	6
2.5.2	Chlorination Procedures	7
2.6	Chlorination Residual Testing	8
3.0	ROUTINE OPERATION	8
3.1	Chlorine Residual	8
3.1.1	General	8
3.1.2	Requirements	9
3.1.3	Determination	10
3.2	Records	11
4.0	EMERGENCY OPERATION	12
5.0	ADVERSE BACTERIOLOGICAL RESULTS	13
6.0	DISINFECTION OF NEW AND REPAIRED MAINS	14
6.1	Preparation	14
6.2	Disinfection of New Water Mains	15
6.3	Disinfection of Repaired Water Mains	18
6.4	Bacteriological Testing	19
7.0	DISINFECTION OF NEW AND REPAIRED RESERVOIRS	20
7.1	Preparation	20
7.2	Disinfection Procedures	20
7.3	Bacteriological Testing	21
8.0	DISCHARGE OF CHLORINATED WATER	22

ABSTRACT

Chlorination of potable water supplies - revised March 1987.

The bulletin is a guideline for the disinfection of potable water and distribution systems. The 1980 version was updated (March 1987) to include the revised American Water Works Association procedures for the disinfection of new and repaired water mains and reservoirs. The bulletin, as before, also provides detailed information on where disinfection is required, minimum chlorine residuals, chlorination equipment, and monitoring.

RÉSUMÉ

La chloration de l'eau potable - document révisé en mars 1987.

Cette publication établit les directives à suivre pour la désinfection de l'eau potable et des réseaux de distribution. La version de 1980 a été mise à jour en mars 1987 afin d'inclure les directives révisées de l'American Water Works Association pour la désinfection des nouveaux réservoirs et conduites principales et de ceux qui ont été réparés. La nouvelle édition, comme l'ancienne, contient également des renseignements détaillés sur les cas où la désinfection est nécessaire, la quantité minimale de chlore résiduel, l'équipement requis pour la chloration, et la surveillance de ce procédé.

ONTARIO MINISTRY OF THE ENVIRONMENT
BULLETIN
CHLORINATION OF POTABLE WATER SUPPLIES

1.0 INTRODUCTION

1.1 Purpose of Bulletin

Disinfection, to kill pathogenic organisms, is the most important step in any water treatment process. In Ontario it is usually accomplished by adding chlorine. This chemical has many other uses in water treatment such as coagulation aid, taste and odour control and maintenance of water quality in the distribution system, but its primary purpose is disinfection. This bulletin is a guideline that outlines the requirements to achieve adequate disinfection and the procedures to follow when it is not achieved. The bulletin also outlines a design standard. New installations should meet the criteria as set out in the bulletin and existing facilities should be brought up to these standards.

1.2 When is Disinfection Required?

Continuous and adequate disinfection is required when the supply is obtained from a surface source; when ground water sources are or may become contaminated, as in fractured limestone areas; when the supply is exposed to contamination during treatment or when emergency conditions such as flooding or epidemic, indicate the need. Disinfection equipment should also be available at those plants where continuous disinfection is not required, to allow temporary disinfection if unsatisfactory or poor bacteriological quality of water is reported. The design of all plants should incorporate suitable connections for disinfecting equipment to be added for this purpose.

1.3 Types of Chlorination

Chlorine when added to water immediately dissociates into hypochlorous acid and hydrochloric acid. The former compound can further dissociate

to hypochlorite ion and hydrogen. Hypochlorous acid predominates when the pH is below 7.5. It is the compound that is the prime disinfecting agent in a free chlorine residual. However, it is very reactive and will quickly combine with certain compounds (e.g. ammonia) and slowly with many other compounds, that may be present in water, to produce a combined chlorine residual (monochloramine, dichloramine etc.). When sufficient chlorine is present so that the reactions that form the combined chlorine are completed, the breakpoint has been reached. The addition of more chlorine will then yield a free chlorine residual.

Of the many regimes of chlorination, simple or marginal chlorination is probably the most common. This also probably is the least effective, especially if it is the only treatment applied to surface water. Chlorine is applied to give an initial total chlorine residual of 0.2 - 0.5 mg/L, predominantly as a combined residual that frequently disappears in the distribution system.

Free residual chlorination produces a much superior disinfecting agent. Sufficient chlorine should be added so that the free residual comprises about 60 to 80 percent of the total residual and it should be maintained through all of the water treatment plant and distribution system. Very high free residuals (super-chlorination) would necessitate at least partial dechlorination, before entering the distribution system, with sulphur dioxide, sodium thiosulphate or activated carbon. The addition of ammonia will produce the more stable but less active disinfectant, chloramine.

If only a chloramine residual is desired, it can be achieved by adding ammonia before the chlorine. However, a much higher dose and/or longer contact time is required to achieve the same degree of disinfection as a free chlorine residual.

Pre-chlorination together with post-chlorination, as required is a frequent mode of operation at Ontario water treatment plants. If organic compounds in the raw water tend to cause formation of chlorinated organics (chloroform, etc) it may be advisable and possible to chlorinate just prior to or after filtration when many organic

precursors may have been removed. However, the bacteriological integrity of the water must receive first priority when considering any modification to chlorination practices aimed at reducing the formation of chloro-organics.

2.0 EQUIPMENT

Chlorination equipment must be readily available at all water treatment plants. This includes all ground water supplies where chlorination is not continuous.

2.1 Capacity

Chlorination equipment shall have a maximum feed capacity at least 50% greater than the highest expected dosage required to provide a free chlorine residual of 1.0 mg/L in the finished water.

2.2 Duplicate Equipment

Chlorine feed equipment (both gas and hypochlorite chlorinators) at waterworks where disinfection is required, should be installed in duplicate, to provide uninterrupted chlorination in the event of a breakdown. In addition, spare parts consisting of at least the commonly expendable parts such as glassware, rubber fittings, hose clamps and gaskets, should be provided for effecting emergency repairs.

For a multi-well supply system requiring chlorination for disinfection, the standby requirements may be met by one portable unit.

2.3 Chlorinators and Controls

Dependable feed equipment, either of the gas feed or positive displacement solution feed type, shall be used for adding chlorine. Automatic proportioning of the chlorine dosage to the rate of flow of water should be provided at all plants, especially where the rate of flow varies without manual adjustment or operation of valves and/or switches. Manual controls for prechlorination may be useful at water

plants manned full time. Where the chlorine demand is not constant, it may also be necessary to either adjust the chlorine dose through a chlorine residual analyzer, or feed a constant chlorine dose and use the chlorine residual analyser to regulate the feed of a dechlorinating agent.

2.4 Gas Chlorination

More detailed guidelines on building design, ventilation, handling and safety equipment, and storage facilities for gas chlorination can be found in the Ministry of the Environment publication "Guidelines for the Use of Chlorine, Sulphur Dioxide, and Ammonia in Water and Sewage Treatment Works in the Province of Ontario" February 1987, Issue No. 1.

2.4.1 Building Design

Gas chlorine equipment (chlorinators, weight scales, chlorine cylinders) must be located in an isolated room or rooms which are above grade at ground level. In larger installations the storage and weighing facilities should be in a room separate from the chlorinators. The construction of the facility should be of fire-resistant and corrosion proof material, have concrete floors and be gas-tight (relative to the rest of the building). All interior surfaces should be coated with a substance impermeable to chlorine gas. Proper ventilation equipment must be provided.

A set of corrosion resistant scales should be available for weighing the chlorine cylinders. Scales for 68 kg (150 lb.) cylinders should be of the low profile type. Non-low profile scales should be recessed in the floor. Safety chains shall be used to retain each cylinder, in storage and on weigh scales, in a safe upright position.

Chlorine should not be stored below ground level and the cylinders must be protected from excessive heat, dampness and mechanical damage. One ton cylinders shall be stored on their sides on level racks.

Where rail cars are used, a dead end siding restricted to chlorine tank cars shall be provided. The tracks must be level and protected by a locked derail and/or a locked closed switch.

Areas containing chlorine and chlorination equipment shall be clearly marked, "DANGER! CHLORINE STORAGE" or, "DANGER! CHLORINE FEED EQUIPMENT" as applicable. The exit doors with panic hardware shall be hinged to open outwardly. There shall be two or more exits if the distance to travel to the nearest exit exceeds 4.5m (15 feet). All exits from the chlorine room and storage area must be to an outside wall. Gas-tight inter-connecting door(s) between these rooms is permitted if they have a common wall.

In gas withdraw systems the temperature in the chlorine storage and scale room shall not be higher, and preferably slightly lower than that in the chlorinator room. The minimum temperature should be 15°C. The gas lines between the scales, chlorinators and injectors shall not be located directly on an outside wall or in a location where low temperatures may be encountered.

2.4.2 Safety Equipment

Each plant shall have readily available, a self-contained or air-supplied respirator of the pressure demand type. One respirator shall be located in a conspicuous location outside the area of probable contamination.

Protective clothing including rubber gloves and slickers, goggles, aprons and safety footwear shall be available for persons handling chlorine.

Eye-wash fountains shall be located as near as possible but outside the area of probable contamination.

All chlorine rooms must have a chlorine leak detector alarm system.

Container emergency kits to repair leaking valves, fusible plugs or the tanks themselves are available from chlorine suppliers. There are different kits for each size of tank and the proper size should be available at each water plant.

It is advisable that a contingency plan be developed to cope with a major chlorine leak. This is especially important when the facility is located in a residential area.

2.5 Hypochlorite Chlorination

It is important that hypochlorite compounds which contain an algicide not be used as a disinfecting agent in potable water systems.

2.5.1 Safety Procedures

Sodium hypochorite, (a liquid) and calcium hypochlorite (a powder) are frequently used to provide chlorination at small municipal water plants and to disinfect mains and reservoirs. Certain safety precautions must be observed in the storage and handling of these compounds.

Calcium Hypochlorite

Certain precautions must be taken when adding granular calcium hypochlorite.

1) Store containers in a clean, cool, dry area away from any combustible material. Spontaneous combustion can result from improper storage. Keep the containers away from moisture, heat and fire. There should be no smoking in this area.

2) Metal drums should be kept upright and should not be dropped, rolled or skidded. Calcium hypochlorite, if dropped, can explode and burn.

3) Empty containers should be thoroughly rinsed with water.

4) When handling calcium hypochlorite it must never have contact with the eyes and it can cause serious burns in the lungs or on damp skin. Face shields with dust masks together with long gloves and other protective clothing must be worn.

5) When measuring calcium hypochlorite a plastic, glass or enameled device that is clean and dry must be used. It should only be mixed with water.

Sodium Hypochlorite

Sodium hypochlorite is much safer than calcium hypochlorite but does require much more storage space and is more costly to transport long distances.

1) There is no fire hazard from the storage of sodium hypochlorite but corrosion from spillage can be a problem if the facilities are not corrosion resistant and cannot be well flushed with water.

2) When handling the chemical, proper clothing (gloves, eye goggles, etc.) shall be worn.

2.5.2 Chlorination Procedures

Where a powdered product is used, hypochlorite solution shall be prepared in a separate tank to allow clarification by settling before it is directed to the solution storage tank serving the hypochlorinator. If the water used to dissolve the granular hypochlorite has a hardness in excess of 100 mg/L, the water should be softened with hexametaphosphate (Calgon) or an ion exchange unit. Periodic purging of the metering systems, with muriatic acid, may be necessary to remove calcium deposits. The acid must be flushed from the system before it is put back into use.

The stability of the hypochlorite solution is increased if the concentration is low; the pH is above 10; iron, copper and nickel content is low; and the solution is stored in the dark at low temperature.

2.6 Chlorine Residual Testing

All surface water supplies should be equipped with a continuous chlorine residual analyzer and recorder as well as a continuous turbidity analyzer and recorder; this is especially important where water near the intake could become polluted. All surface water plants should at least be equipped with an alarm system that would indicate when the chlorination equipment malfunctions.

Ground water sources, where poor water quality and/or minimum supervision indicates a possible health hazard, should have an automatic chlorine residual analyser and recorder equipped with a high and low residual alarm or at least an alarm system that would indicate when the chlorination equipment malfunctions.

All installations must be equipped with a permanent standard chlorine residual testing device. It is preferable to use a DPD comparator test kit, an amperometric titrator or equivalent. The amperometric titrator can be used to check the accuracy of a continuous chlorine residual analyzer. The above methods can be used to measure a free chlorine residual in the finished water, the distribution system or in the stand-pipe when an emergency or other circumstances require a free residual.

3.0 ROUTINE OPERATION

3.1 Chlorine Residual

3.1.1 General

Chlorine can be present in water as either a free or a combined residual. The bactericidal effectiveness of both residual forms is markedly reduced by high pH or turbidity, while it is enhanced by a higher temperature or a longer contact time. A free chlorine residual, while a much more effective disinfectant, also readily reacts with ferrous iron, manganese, sulphides and organic material to produce compounds of no value for disinfection.

3.1.2 Requirements

Chlorination is required for all surface waters and many ground waters. A total chlorine residual of at least 0.5 mg/L after 15 minutes (preferably 30 minutes) contact time after the filter and before the first consumer will be provided at all times. Exceptions are: 1) surface water treatment plants achieving low uniform turbidities (1 FTU or less) together with a contact time of at least 2 hours, and 2) ground water supplies proven free of hazardous bacterial contamination. In these two situations a minimum total chlorine residual of 0.2 mg/L is allowable. These are minimum acceptable residuals not target or objective residuals. The chlorine residual should be differentiated into its free and combined portions for recording purposes at least to get historical information and when problem solving. It is preferable that most of the residual be a free residual. Adequate disinfection may not occur at these minimum levels if the pH is above 7.5 or the turbidity above 1 FTU.

As circumstances demand, the minimum requirements for chlorine residual and/or contact time may be increased.

The chlorine residual test must be performed as frequently as needed to ensure that an adequate chlorine residual is maintained at all times. Such considerations as raw water quality and the resultant variation in chlorine demand, and changing flow rates must be taken into account.

The accuracy of an automatic chlorine residual analyzer shall be checked at least weekly. This shall be accomplished using the amperometric titrator or equivalent. The results of the check shall be inscribed on the recording chart along with the date and operator's initials opposite a mark indicating the time of the check.

A chlorine residual should be maintained in all parts of the distribution system. This will do little to protect the supply in the event of a main break or some other disaster but should control

nuisance growths. The residual should be differentiated into its free and combined portions. The pH should be known and if it is a variable parameter it should be measured and recorded so that the major chlorine constituents in the water can be determined.

The amount and type of chlorine residual present when routine bacteriological samples are taken should be recorded, because this allows a more complete evaluation of the condition of the distribution system. Recording this information on the laboratory submission form may facilitate the comparison.

3.1.3 Determination

A representative sample of chlorinated water should be tested. From a tap, the water should be kept running for 5 minutes before taking the sample.

The time when the chlorine residual test should be made depends on where the sample was taken. If the sample has just been chlorinated it should be held for 15 minutes, to simulate the minimum contact time, in a covered demand-free container away from light and heat. However, a sample from the distribution system or finished water after a contact chamber should be tested immediately.

Determination of a chlorine residual should be done by one of the methods outlined in the most recent Standard Methods (16th Edition, 1985) which are preferable to the orthotolidine test. This method is no longer in standard methods due to the toxic nature of orthotolidine. At present, the most widely used methods are the DPD (diethyl-p-phenylene diamine), both titrimetric and colorimetric, and the amperometric titration. For small water treatment plants or field testing a DPD comparator kit is acceptable.

When using the DPD colorimetric (comparator) test, for free and total chlorine residuals, a few important procedures must be observed.

1) The glass cell must be thoroughly rinsed after each test, since any trace of the potassium iodide (Tablet #3) will cause the chloramine colour to develop in the next test for free chlorine.

2) To facilitate dissolving the tablets, they can be crushed while still in their tinfoil packets (pillows may dissolve faster).

3) Disintegrate tablet #1 in a few drops of the sample in the test cell. Fill the test cell with the required amount (often 10 mL) and mix rapidly.

4) The free chlorine residual must be read within 30 seconds of adding the sample to the cell.

5) The total chlorine residual is determined by adding tablet #3 (crushed) to the same sample in the test cell, mixing, waiting 2 minutes for the full colour to develop and then reading the results in the comparator.

3.2 Records

Minimum records shall include:

1) Daily records of the chlorine used and scale readings;

2) Results from all chlorine residual tests, together with the flow rate and chlorine feed rate and the time of testing;

3) The daily water consumption and the chlorine dosage in milligrams per litre;

4) Details on chlorine orders, chlorine on hand, and possibly cylinder changes;

5) Monthly and yearly summaries of chlorine consumption and feed rates.

For surface supplies it is desirable to record daily air and water temperatures and weather conditions e.g. rain, cloud, sunny, snow etc. together with wind direction and strength.

4.0 EMERGENCY OPERATION

At all facilities supplying municipal drinking water, a procedure to follow in case of emergency (i.e. plant malfunction) must be developed. A list of procedures for the operator to follow must be posted in a prominent location in the plant.

This list must include:

1) The order not to pump unchlorinated or inadequately chlorinated water to the distribution system;

2) The name, address and telephone number of:

   a) Senior supervisory personnel,

   b) Medical Officer of Health and an alternative in the regional health unit if the Medical Officer of Health cannot be reached,

   c) The local M.O.E. District Officer and an alternate,

   d) Chlorinator service company (to be called only if chlorinator needs servicing),

   e) Chlorine supplier (to be called when chlorine required or when tanks malfunction);

3) The exact procedure to follow in order to increase the total chlorine residual leaving the plant to a minimum of 1.5 mg/L.

Wherever chlorination is required, the Ministry of Environment and the Medical Officer of Health must be notified immediately if unchlorinated or inadequately chlorinated water (total residual below 0.2 or 0.5 mg/L or level required) is directed to the distribution system. If this has

occurred the Ministry of Environment may require the chlorine feed rate to be increased to provide a 1.0 mg/L or higher residual leaving the plant. Extensive flushing may also be required to carry the residual through the distribution system. Depending on the circumstances additional steps may be required.

When the chlorine residual is increased all customers who may be adversely affected must be notified.

5.0 ADVERSE BACTERIOLOGICAL RESULTS

When the results from bacteriological samples collected from the distribution system indicate "unsafe water quality" on the basis of the Ontario Drinking Water Objectives (ODWO) [by a) presence of fecal coliform bacteria or b) the number of total coliform bacteria five or more per 100 ml or when determined by the P-A method positive results within 48 hours] the procedures to follow immediately are:

1) Notify the Ministry of the Environment (increased chlorine residuals may be advised),

2) Collect special samples (ODWO, p.11) to confirm the results and determine the extent of the contamination. Chlorine residuals should also be recorded.

If these samples still show unsatisfactory water quality, the Medical Officer of Health and the Ministry of the Environment must be notified and the chlorination increased to provide a total chlorine residual of 1.0 mg/L or a free chlorine residual of 0.2 mg/L at the end of the distributing system. Systematic flushing or swabbing may be necessary in order to achieve and maintain a residual at the ends of the distribution system.

A thorough study of the treatment plant and/or distribution system should be undertaken to determine the cause of the adverse bacteriological results. If the conditions warrant it the Ministry of Environment should recommend to the Medical Officer of Health that a boil-water advisory be issued.

When the bacteriological samples indicate "poor water quality" [total coliform bacteria present at levels below five per 100 ml or positive P-A results after 48 hours, in more than 10% of the monthly samples or other indicator bacteria (see ODWO, p.12)] the Ministry of the Environment may recommend some of the following procedures:

1) Initiate chlorination on an unchlorinated supply,

2) Increase the chlorine residual requirements in the finished water to 1.5 mg/L or more, and maintain the level until notified by MOE,

3) Establish a total or free chlorine residual to the end of the distribution system,

4) Disinfect the distribution system as for new mains (Sec. 6.2),

5) Undertake a thorough resampling of the distribution system which should continue until the water quality is again acceptable.

6.0 DISINFECTION OF NEW AND REPAIRED MAINS

6.1 Preparation

Chlorine is predominantly a surface-active disinfectant that will not penetrate debris rapidly to kill microorganisms. This debris may also react with the chlorine to reduce its disinfecting power. For these reasons, prior to disinfection of new or repaired works, all the debris must be removed. This can usually be achieved by extensive flushing with potable water, with a flow of at least 0.8 m/s (2.5 ft/s), although heavy particles and large mains may require considerable higher velocities. In these cases flushing with foam swabs is advisable. The minimum velocity (0.8 m/s) can be produced as follows:

Pipe Diameter mm (in.)	Flow L/s (igpm)	Diameter of tap on main mm (in)*
100 (4)	6 (80)	24 (15/16)
150 (6)	14 (180)	35 (1 3/8)
200 (8)	25 (330)	48 (1 7/8)
250 (10)	39 (500)	59 (2 5/16)
300 (12)	56 (730)	72 (2 13/16)
400 (16)	100 (1300)	92 (3 5/8)

* no significant length of discharge piping and a 275 KPa (40 psi) residual pressure in water main. A 64 mm (2½ inch) opening on a fire hydrant with a residual pressure of 275 KPa (40 PSI) will discharge about 63 L/s (800 igpm).

It is important to seal off pipe openings against the ingress of animals during pauses in construction to avoid problems with the disinfection process.

6.2 Disinfection of New Water Mains

There are three procedures outlined in the AWWA Standard C601-81.

a) Tablet Method

This procedure must not be used on solvent-welded plastic or screwed-joint steel pipe due to the danger of fire or explosion from the reaction of calcium hypochlorite with the joint compounds.

This method is best suited to short, small diameter mains [up to 300 mm (12 inches)]. Since preliminary cleaning must be forgone, it is absolutely essential that during construction, the pipe interior remains clean and dry. Calcium hypochlorite granules and tablets are placed in the water main as it is being constructed and then the main is filled with potable water when the installation is complete.

Calcium hypochlorite granules are placed upstream in the first section of pipe, at the beginning and end of each branch and at 150 m (5 ft.) intervals. The quantity of calcium hypochlorite granules required each location are as follows:

Pipe Diameter mm (in.)	Calcium hypochlorite granules g (oz.)
100 (4)	15 (0.5)
150 (6)	30 (1)
200 (8)	60 (2)
300 (12)	120 (4)
400 & larger (16+)	240 (8)

The calcium hypochlorite tablets must be placed in each section of pipe and also in each hydrant, hydrant lateral or other connection. The number of 5 g tablets required for each pipe section shall be adequate to provide a dosage of 25 mg/L and can be determined with the formula:

No. tablets = $0.000006\ D^2\ L$
where D = diameter of pipe in millimetres
L = length of pipe in metres
(based on 3.25 g available chlorine per 5 g tablet)

The number of tablets is always rounded up to the next highest whole number. The tablets are attached to the top of the pipe using an approved adhesive with equal number at each end of the pipe section.

The main is slowly filled [flow less than 0.3 m/s (1 ft/s)] to prevent washing the tablets to the end of the main. The contact time will be at least 24 hours and if the water temperature is below 5°C (41°F) it will be at least 48 hours.

b) Continuous Feed Method

An optional addition to this method is to place calcium hypochlorite granules in each section of pipe as outlined in the previous section. The purpose is to provide a strong chlorine concentration in the first flow of water especially in the pipe joints.

The main is filled and flushed with potable water (minimum flow 0.8 m/s). The flow is then adjusted to a constant known rate and sufficient chlorine is added to produce a free chlorine residual of 25 mg/L. This is achieved by injecting a hypochlorite solution into the inflowing water or using liquid chlorine through a solution-feed chlorinator and booster pump. The amount of chlorine required for every 30 m (100 ft) of pipe would be as follows:

Pipe Diameter mm (in.)	100% Chlorine g (lb) oz.	1% Chlorine* solution L (imp. gal)
100 (4)	6 (0.013) 0.2	0.59 (0.13)
150 (6)	14 (0.030) 0.5	1.36 (0.30)
200 (8)	24 (0.054) 0.9	2.45 (0.54)
250 (10)	38 (0.085) 1.4	3.86 (0.85)
300 (12)	54 (0.120) 1.9	5.45 (1.20)
400 (16)	98 (0.217) 3.5	9.85 (2.17)

* a 1% chlorine solution can be prepared with sodium or calcium hypochlorite. With the latter (70% available chlorine) use the relationship 36g in 1000 L of water.

The contact period shall be at least 24 hours, at which time the free residual chlorine must not be less than 10 mg/L or the procedure must be repeated.

c) Slug Method

This method is suitable for large, long mains where the continuous feed method is impractical. It consists of placing calcium hypochlorite granules, filling and flushing the main, and finally chlorinating with a slug of highly chlorinated water.

Calcium hypochlorite granules are placed in each section of pipe when it is installed as described in the tablet method. The main is then filled and flushed with a minumum velocity of 0.8 m/s. The flow into the new main is then adjusted to a constant rate and sufficient chlorine is added to achieve not less than 100 mg/L free chlorine residual. The chlorine is added continuously so that a slug of chlorinated water is produced. Additional potable water is added so that the slug moves down the new main at a rate that will provide a contact time of at least three hours.

The free chlorine residual must be monitored as it progresses along the main. If the free chlorine residual falls below 50 mg/L, additional chlorine must be added at the head of the slug to re-establish the 100 mg/L free residual.

As the slug passes down the main all valves, hydrants and side branches shall be exposed to the disinfecting solution.

6.3 Disinfecting Repaired Water Mains

When a leak is minor and the water in the main always has a positive pressure, no disinfection is required after the repair is complete. However, with a more serious break the main must be disinfected before being put back into service. AWWA Standard, C601-81 lists two alternatives. If the broken main need not be put back into service immediately the methods outlined for new mains would ensure better disinfection.

When an existing main is opened the excavation is usually extremely wet and muddy. To reduce the chance of contaminating the water system liberal quantities of calcium hypochlorite granules or tablets should be added to the open trench.

a) Swabbing and Flushing

This procedure is the minimum that may be used. The interior of all pipes and fittings must be brushed or sprayed with a 1% hypochlorite solution as they are installed. The chlorine solution can be sprayed on with a small pressurized tank. This is followed by flushing, preferably in both directions, until the coloured or dirty water is eliminated.

b) Slug Method

Where possible, the following method should be used. The main with the break is isolated and repaired, then flushed and if necessary foam swabbed to remove all debris. Chlorine is then introduced, as in Sec. 6.2 c), except that the residual may be increased to 300 mg/L and the contact time reduced to as little as 15 minutes. After the contact period the main is well flushed and then put back into service.

6.4 Bacteriological Testing

The new or repaired main must be well flushed with potable water, to remove the heavily chlorinated water. The chlorine residual should be very close to the residual normally carried in the distribution system. Bacteriological samples must then be taken to test the effectiveness of the disinfection process. Using a fire hydrant or hose for sampling may result in spurious results. Better samples may be obtained from blowoffs with sampling taps or corporation stops along the main connected to a reusable copper goose neck. A sample shall be collected from the main and each branch. If the main is very long several samples should be collected along its length. In distribution systems that normally carry a free chlorine residual one sample or a set of samples (in a long main) is sufficient. However, in all other systems or if trench water had entered the main a second sample or set of samples should be collected after 16 hours. More samples may be required on a regional basis or when conditions warrant such action. Samples should be collected in accordance to the Ministry of the Environment publication "A Guide to the Collection and Submission of Samples for Laboratory Analysis". A main is considered adequately disinfected if there are no detectable coliforms in any of the samples.

New mains must not be put into service until the coliform tests are acceptable. The disinfection process must be repeated if they are not. If the length of time between disinfection and use of the water is considerable, it may be advisable to flush the main and retest prior to customer use.

If possible, repaired mains should also be kept out of service until acceptable results are received. This is seldom possible but if fecal contamination of the main is known or suspected it must be done to prevent a public health hazard. If the test sample(s) are positive for coliforms the disinfection should be repeated but at least daily samples should be taken until two consecutive negative samples are recorded.

Note: The high velocities required for adequate flushing may disturb sediments in existing mains which may lead to that sediment being carried into the new or repaired main. Since this could be a source of adverse sample results, it may be advisable to sample the water entering the new or repaired main.

7.0 DISINFECTION OF NEW OR REPAIRED RESERVOIRS

7.1 Preparation

As with water mains, the interior of storage facilities must be cleaned and free of debris before attempting the disinfection process. This is accomplished by washing down the walls and floors with high pressure jet cleaning equipment and/or long handled brushes. All the debris must be rinsed from the tank interior before disinfection.

7.2 Disinfection Procedures

There are three methods for disinfection in the AWWA Standard D105-80 and they are as follows:

a) First Method

This is suitable for tanks where gross contamination has occurred. The tank is filled with potable water to which has been added sufficient chlorine to result in a 10 mg/L free residual at the end of the contact period. If the chlorine is added with gas chlorination equipment or a chemical feed pump (sodium hypochlorite) to all of the water that fills the tank, a six hour contact period is adequate. However if the chlorine is added in bulk prior to filling the tank as sodium hypochlorite (water depth must be between 1/3 and 1 metre) or calcium hypochlorite granules or crushed tablets, the contact period must be at least 24 hours.

After the retention period the water is either drained to waste or partially drained and refilled to reduce the chlorine residual to a level acceptable for distribution (usually not more than 2 mg/L free chlorine). Use of the water in the tank will depend upon acceptable bacteriological and water quality results.

b) Second Method

This method can be used in a relatively clean reservoir, such as following routine cleaning or repair. The walls up to the overflow level, floor and stanchions are sprayed with a 200 mg/L chlorine solution. All piping except the overflow system shall be sprayed with the strong chlorine solution, or shall have sufficient chlorine added to result in a minimum residual of 10 mg/L when filled with water. To achieve disinfection, surfaces and piping that will be in contact with potable water must not be rinsed or flushed of the disinfecting chlorine solution until at least 30 minutes has passed. After this contact period, the piping system is flushed and the tank filled with potable water, and after satisfactory water quality tests, including bacteriological, the tank is put into service.

c) Third Method

Water containing 50 mg/L chlorine is placed in the tank to such a depth (about 5% of total volume) that when the tank is filled the a free chlorine residual of not less than 2 mg/L can be measured after the contact period of 24 hours. The chlorine can be added by any of the methods in the first technique. The water containing the 50 mg/L chlorine is held in the tank for at least 6 hours before the tank is filled. The full tank in turn is allowed to stand for 24 hours after which the tank may be put into service without draining the water used to disinfect it, subject to satisfactory bacteriological testing and acceptable water quality.

7.3 Bacteriological Testing

Prior to placing the new or repaired reservoir into service, following chlorination and subsequent procedures to reduce the residuals, samples must be taken from the full facility for bacteriological analysis to ensure adequate disinfection. If a free chlorine residual is usually carried in the system only one set of samples is required but in all other systems a second set of samples should be collected after 24 hours.

The bacteriological samples should show no detectable coliforms before a reservoir is put into service. If coliform bacteria are detected, the disinfection process should be repeated until satisfactory results are obtained. Frequent sampling is to continue until two negative results are recorded.

During the filling process, high flows in the distribution system can resuspend sediments. It is recommended that bacteriological samples be taken of the "potable" water flowing into the tank during the disinfection and testing processes to determine if coliforms are present.

8.0 DISCHARGE OF CHLORINATED WATER

Chlorinated water, as used in the disinfection of water mains and reservoirs, can be very toxic to aquatic organisms and it should not be disposed of without careful thought to its effect on the receiving water or sewage treatment plant (STP).

Chlorinated water can be discharged to:

1) Sanitary Sewers - This is a safe course to follow especially if the volume is not great and there is a considerable distance from the point of addition to the STP. However, if there is a large volume, e.g. with a reservoir, it is essential to contact the municipality to ensure that the operation of the STP is not adversely affected by a hydraulic overload or a massive slug of water with a high chlorine residual.

2) Receiving Waters - This can be detrimental to aquatic life and many fish kills have resulted. Water with a free chlorine residual should not be discharged to a stream or lake. If a combined chlorine residual is present, the concentration at the edge of the mixing zone (where allowed) should be below 0.002 mg/L.

3) Storm Sewer - This should be thought of as directly connected with the receiving water and the same restrictions should apply, even though there could be considerable dilution during wet weather.

4) Drainage Ditch - Discharge to an open ditch is a good alternative, especially if the point of addition is a considerable distance from the receiving water and the ditch is unlined and is full of weeds and other organic material. Sunlight and high temperatures would help to dissipate the chlorine quickly.

If the above conditions cannot be met, a slow discharge of the chlorinated water to a sanitary sewer or ditch can be used. This is easier and cheaper than dechlorination. If dechlorination is necessary (i.e. with direct discharge to a small stream), there are several chemicals that can be used effectively. Adequate mixing and dosage of the chemical with the chlorinated water must be ensured. The amount of dechlorination chemical required can easily be determined from the following equation.

Excess chlorine residual x Factor = Dechlorination chemical required.

This can be worked out in mg/L, lbs or whatever units are appropriate.

There are five chemicals that can be used to dechlorinate the water:

1) Hydrogen Peroxide - (Factor = 0.479) - This is probably the best chemical when discharging to an environmentally sensitive watercourse. It is cheap and an overdose will only add more oxygen to the stream.

2) Sulphur Dioxide - (Factor = 0.901) - This chemical is cheap but it will slightly lower the pH in the receiving water.

3) Sodium Thiosulphate - (Factor = 2.225) - This will cause some sulphur turbidity but an excess is harmless.

4) Sodium Sulphite - (Factor = 1.775) - Excess will lower the dissolved oxygen in the stream.

5) Sodium Pyrosulphite - (Sodium Metabisulphite) - (Factor = 1.338) - Excess will lower the dissolved oxygen in the stream.

For example, a total chlorine residual of 21 mg/L measured in a disinfected water main of 11,000 L (2400 gal) for discharge at only 1 mg/L Cl_2 could be neutralized with hydrogen peroxide. The dosage required would be 20 mg/L x 0.479 = 9.6 mg/L and the total amount needed would be 9.6 x 11000 = 105.6 gm of H_2O_2. This would represent, in terms of 35% commercial grade hydrogen peroxide (sp. gr. 1.13 g/mL),

$$105.6 \times \frac{100}{35} \times \frac{1}{1.13} = 267 \text{ mL of concentrate.}$$

HG/rmg
00872-08A.1
DW/MUNWTR